BANGALORE DISTRICT.

Notice dated 31st December 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive gineer, Bangalore Division, up to 2 P.M., dated 20th January 1930, for the Improvements he Epidemic Diseases Hospital at Bangalore. An approximate estimate of quantities iven below. These quantities are not guaranteed. The work should be completed by the of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's e at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the cutive Engineer. The tenders should be accompanied by a statement in the form given w, showing the rates at which the different items specified will be executed.

(*aa*) Tenders quoting percentages below or above estimates will not be accepted.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government missory Notes as earnest money and be superscribed "Tender for the Improvements to the demic Diseases Hospital," Bangalore, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who not bind himself to accept the lowest or any tender or to assign any reason whatever the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be uired to execute the usual contract bond in default of which his tender will be considered celled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be ed on the notice board in the Executive Engineer's office in due course. No enquiries rding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be rned.

Improvements to the Epidemic Diseases Hospital, Bangalore.

ial).	Items of work	Per	Quantity	Rate Rs.	a.	p.
	(1) *Sub-Assistant Surgeon's and Compounder's Quarters.*					
1	Removing the country tiled roof with its reepers 1" thick from over the roof of the above two quarters.	Sqr.	23·96			
2	Roofing with 1st Class Mangalore tiles over teak reepers 1" thick with required quantity in addition to the available old reepers used in doubles.	„	24·70			
3	New ridge tiles set in mortar	R.ft.	180			
	(2) *Coach Godowns.*					
1	Chunam plastering inside the room, after scraping the existing badly worn out mud plaster.	Sqr.	3·50			
2	Dismantling the wall and clearing rubbish. ...	C.ft.	23			
3	Providing burnt stone slabs	S.ft.	15			

Serial No.	Items of work	Per	Quantity	Rs.
	(3) Government Chattram attached to Epidemic Disease Hospital.			
1	Removing the Sudda earth from over the mantap roof of the centre portion (in front) of the chattram and carting it to a ditch nearby with a lead of a furlong nearly.	Sqr.	10·67	
2	Filling the crevices with brickbats and for the undulations of the slabbed roof with required jelly concrete.	"	10·67	
3	Roofing with 4" concrete bed with 2 courses of flat tiles set in mortar over the mantap slabbed roof including plastering above.	"	10·67	
4	Parapet wall construction with brick in clay and plastering, complete.	R.ft.	161 1/8	
5	Dismantling the mud wall and clearing the rubbish to the ditch nearby.	C.ft.	3,171	
6	Removing the Mangalore tiled roof with its reepers and rafters and stacking in a place.	Sqr.	6·25	
7	Construction with brick in mud	C.ft.	2,542	
8	Chunam plastering	Sqr.	48·66	
9	Providing new teakwood battened doors in teak frame 1¼" thick.	S.ft.	144	
10	Providing new teakwood windows with battened shutters and 5/8" iron bars.	"	98	
11	Providing Lintal slab 4" to 6" thick	"	230	
12	Flooring with jelly concrete 3" to 4" thick for inside the rooms.	Sqr.	10·64	
13	Fine mud plastering for the existing cross walls, after the old plaster work.	"	10·80	
14	Roofing with old Mangalore tiles over the old available reepers and rafters.	"	6·25	
15	Mortar band along the slope of roof ...	R.ft.	75	
	(4) Kitchen Block Work.			
1	Dismantling the brick walls and clearing rubbish ...	C.ft.	374	
2	Removing the worn out doors	Each	2	
3	Removing the zinc sheet roof with its worn out rafters	Sqr.	4·27	
4	Removing the worn out flooring tiles	"	2·30	
5	Earthwork excavation for new kitchen block ...	C.yd.	14	
6	Stone in mud	C.ft.	524	
7	Burnt brick in mud	"	701	
8	Old brick in mud	"	129	
9	Chunam plastering	Sqr.	16·51	
10	Mortar pointing to basement	"	0·87	
11	Flooring with available tiles over fresh concrete and cement pointed.	"	1·70	
12	Flooring with burnt stone slabs over concrete bed and cement pointed.	"	0·95	
13	Providing new teakwood door with battened shutter ...	"	46	
14	Providing windows in teak frame, with battened shutter and 5/8" iron bars.	"	26	
15	Providing lintel slabs 4" to 6" thick	"	51	
16	Teakwood wrought and put up	C.ft.	25·38	
17	Roofing with old available corrugated zinc sheets with	Sqr.		

No.	Items of work	Per	Quantity	Rate Rs.	Rate a.
	Brunt brick in mortar	C.ft.	84		
	Burnt stone slabs dressed and pointed	S.ft.	20		
	Cement plaster all round ½" thick	Sqr.	0·48		
	Whitewash two coats	"	16·32		
	Miscellaneous works. Lepar Asylum Male and Female Wards.				
	Removing the existing worn out Mangalore tiled flooring.	Sqr.	10·94		
	Providing Kadapa slabs over mortar bed and cement pointed.	"	10·94		
	Providing expanded metal ½" mesh in teak patties, fixed to the existing window frames.	S.ft.	360		
	Removing the worn out cement plaster flooring and clearing rubbish.	Sqr.	2·40		
	Providing Kadapa slabs over mortar bed and cement pointed.	"	2·40		
	Drainage all round the two main wards by providing "V" shaped drain, with stone slabs, concrete and cement pointed, with necessary works.	R.ft.	400		
	Other wards.				
	Two coats of oil painting chocolate colour to the wall, with necessary scraping and two priming coats of linseed oil.	Sqr.	85·06		
	Providing "V" shaped drain in slab, with surki concrete, cement plaster and pointing to collect the waste water of the wards including earthwork.	R.ft.	170		
	Construction of masonry cistern to collect the drainage Dater of the wards brick in mortar.	C.ft.	203		
	Earthwork excavation for the above cistern ..	C.yd.	16		
	Jelly concrete filling in foundation	C.ft.	61		
	Burnt stone slabs dressed and pointed	S.ft.	122		
	Cement plastering all round ½" thick	Sqr.	2·88		

Abstract Notification dated 31st December 1929.

Attention of the public is invited to notice calling for sealed tenders for the construc- Amildar's quarters at Closepet, published on page 25 of Part VI of the *Mysore Gazette*, 2nd January 1930.

The last date for receiving is 13th January 1930.

Abstract Notification dated 31st December 1929.

Attention of the public is invited to notice calling for sealed tenders for restoring Ikunte Tank Reg. No. 252 of Nelmangala Taluk, published on page 24 of Part VI of the *re Gazette*, dated 2nd January 1930.

The last date for receiving is 13th January 1930.

H. R. VENKATASUBBA RAO,
Executive Engineer.